



Project:	OnCenter Surface Lot
Project Owner:	Onondaga County
Project Location:	801-813 S. State St.
Sewershed:	Clinton/Lower MIS
GI Technology:	Porous Pavement, Tree Trench
Capture Area:	134,000 sq. ft.
Runoff Reduction:	2,360,000 gal/yr
Year Completed:	2011
Construction Cost:	\$529,040
Prime Contractor:	Economy Paving

## FACT SHEET

### OnCenter Surface Parking Lot

**Project Description:** The OnCenter surface parking lot was the site of a stormwater retrofit project that repaved the existing parking lot with a combination of porous asphalt and traditional asphalt. In addition to the pavement resurfacing, the project features the design and construction of an infiltration trench along three sides of the parking lot to manage runoff from the entire lot as well as from adjacent streets. The project also features a new tree infiltration trench and a new section of sidewalk. The green infrastructure installed in this lot captures 2.36 million gallons annually.

This project took place at the surface parking lot across the street from the historic War Memorial Arena. The OnCenter is home to countless entertainment attractions for local, regional, and national audiences. Since 1992, the OnCenter has been the premiere convention location for the region.



OnCenter Parking Lot before Construction



Porous Asphalt



OnCenter Parking Lot after Construction Complete